


42" MINIMUM FINAL PAVEMENT WIDTH,  
ROTOMILLING IS AN ACCEPTABLE  
ALTERNATIVE TO MINIMUM PAVEMENT WIDTH



## TYPICAL TRENCH SECTION

### NOTES:

1. PAVING SHALL COMPLY WITH CITY OF BOULDER SPECIFICATIONS.
2. MINIMUM COVER TO BE BELOW OFFICIAL STREET GRADE.
3. MINIMUM DISTANCE BETWEEN EDGE OF TRENCH AND EDGE OF ASPHALT, OR LIP OF CURBLINE, SHALL BE 3 FEET.
4. REFER TO DRAWING NO. 4.04 FOR PAVEMENT RESTORATION FOR PAVEMENT LESS THAN 3 YEARS OLD.
5. ON STATE HIGHWAYS, REFER TO CDOT UTILITY REQUIREMENTS.

### TRENCH WIDTH

PIPE DIAMETER	MINIMUM WIDTH	MAXIMUM WIDTH
6"	1'-6"	2'-6"
8"	1'-8"	2'-8"
12"	2'-0"	3'-0"
16"	2'-4"	3'-4"
20"	2'-8"	3'-8"
24"	3'-0"	4'-0"

DRAWN BY: JSH  
CHECKED BY: RJH  
  
APPROVED BY:  
DIRECTOR OF PUBLIC WORKS

CITY OF BOULDER, COLORADO

ISSUED: JULY 2, 1998  
REVISED: OCT. 17, 2000

UTILITY TRENCH  
WIDER THAN 16"

DRAWING NO.  
4.02